



## BUTTON: Detector Development at Boulby Underground Lab

Workshop on Hybrid Cherenkov/Scintillation Detector Technologies

3-5<sup>th</sup> June 2025

On behalf of the BUTTON collaboration

James Gooding

[jgooding@liverpool.ac.uk](mailto:jgooding@liverpool.ac.uk)

University of Liverpool



UNIVERSITY OF  
LIVERPOOL



# Contents

---

- I've removed intro slides for you're benefit
- The BUTTON collaboration and design goals
- Development and construction of subsystems
- Where we stand currently
- Measurements
- BUTTON future projects



# BUTTON Collaboration



Boulby collaboration meetings in UK and the US 2024.




58 members across 17 institutions in the UK and U.S.

Funded in the UK by STFC from the UKRI Fund for International Collaboration and the MoD


# BUTTON development goals/design intent

- Flexibility to test different technologies
- Advanced photosensors
- Advanced fill media
- H<sub>2</sub>O -> Gd-H<sub>2</sub>O -> WbLS -> Gd-WbLS -> future fills (LS?)
- Building scientific capability at Boulby underground lab



# BUTTON UK development


- BUTTON is housed in Boulby ICL mine in the northeast of the UK.
- Building scientific capability at Boulby underground lab is a key goal of the BUTTON experiments with Boulby being a strong candidate to home future experiments such as XLZD
- How does one build such an experiment in a mine like this... BUTTON has proven that we can!





Science and  
Technology  
Facilities Council

# Boulby Underground Laboratory



The UK's deep underground science facility operating in a working potash and salt mine.

Surface support and staging building

Office space, chemistry & clean prep lab, storage and staging space, IT room, conference room,

3000m<sup>3</sup> Outside Experimentation Area

BUGS+ Material screening

**Boulby Underground Lab Facilities 2021:**  
 >4000m<sup>3</sup> class 1k & 10k clean room lab space  
 100Mb Internet AC, Air filtration, 5T & 10T lifting, LN generation, fume hood & clean prep  
 3000m<sup>3</sup> Outside Expt. Area. Power & internet

**1.1km depth** (2805 mwe). With low background surrounding rock-salt


**Operated by the UK's Science & Technology Facilities Council (STFC)** in partnership with the mine operators ICL-UK

**Reduction of cosmic ray flux vs surface** ( $10^6$ )

# The simplified schematic

## Water system development

- Gd separation or targeted removal of all other impurities
- Future WbLS compatibility
- Flexibility
- Scalability
- Automation/safety
- “Salt mine safety factor”






# Water system development



The water system for the BUTTON experiment has been developed and is currently being built and tested in Liverpool by myself and Kieran Bridges




PVDF pipework for heightened compatibility for future fill media.

# Construction





Production of the 316L PSUP was undertaken by Liverpool University workshop. This is modular for the later inclusion of advanced photosensors.



Custom data acquisition and electronics system is installed in the lab.

# Passivation -Electropolishing






# Passivation -Re-passivation

---




# Liner

- Very thin polythene
- Two revisions made, both tested for fit and stretching on frame
- Manufacturing was challenging due to size/material
- Installation was challenging due to space constraints and fixturing



A fold is made at each corner of the octagonal liner



# Tank Construction





Before



During Construction

Jan 2024 – Tank build commenced



Berm in and Insulation on!

# Initial Fill



## Dec 2024

An initial water fill was commenced to ensure

- Floor loading
- Tank integrity
- Feed and drain plumbing

And to wash debris from the tank.







The tank was then inspected, cleaned and passivated in areas with defects. Before the experiment starts the tank will be flushed 3 times



# PMT installation storyboard

Jan 2025




15/24

April 2025

# Current Status



Tank PMTs installed



Tank is now light tight



Cabling to the DAQ  
complete



PMTs powered on 95/96  
good (failure indicative  
of a loose connection)




Water system nearing  
completion



Calibration systems are  
being finalized and  
prototyped

# Measurements




# Measurements – Radioactive Calibration Sources

- AmBe – radioactive... - shipping from the US imminently
- $^{208}\text{Tl}$  – delayed till end of year



## Team:

- Steven Dazeley, Slava Li, Sean Durham at LLNL.
- Igor Jovanovic (U Michigan) –  $^{208}\text{Tl}$  and switchable AmBe. Possible future experimental source such as the  $\text{Am}^{13}\text{C}$  6.1 MeV gamma-rays
- Christopher Mauger (U. Penn), Jan Boissevain (mechanical E, U. Penn) and Rick Van Berg (Electrical E, U Penn)

## Untagged AmBe and 2.6 MeV $^{208}\text{Tl}$






## Tagged AmBe





# Measurements – Light Sources

- Attenuation arm... (real time Gd water cleanliness)
- Simultaneous attenuation and scattering length measurement over full optical spectrum
- Isolation from atmosphere (oxygen)
- Delivery BUTTON late 2025




# Measurements – Light Diffusers



- HK diffusers
- Disco ball diffuser (ANNIE based)



Four diffusers should illuminate each PMT, albeit at different angles  
Emission half-angle around 35° in water



Steve Boyd





# Other measurements

- Pe/MeV
- Muon response
- LAPPD timing separation




# Other R&D

- Fill media/cocktails etc
- LAPPD
- Boulby development



Glasgow LAPPD test stand


## Boulby Development Project Task 1: Site and design Development.




Stage 1: Clean manufacturing and multi-science lab in salt (1.1km) - 2028

Stage 2: Full depth science lab in Polyhalite (1.3km) ~2030+

A new lab @ Boulby



DRAFT: 2-stage Designs



Total volume (Stage 1 + stage 2) ~120,000m<sup>3</sup>

~(30m)<sup>3</sup> main cavity


Excavations for stage 1 of expansion currently expected to begin mid-2024.

# Future Plans BUTTON/Boulby

Focussing on the a 10.5x10.5m tank

## Boulby Development Project: Stage 1 Excavation

Progress  
August 2024



Stage 1  
Functional  
Design

Excavation well underway. Completion mid 2025 (Outfitting ~2028)

# Future Plans BUTTON 1kT


40% photo coverage tank possible?

Focussing on the a 10.5x10.5m, 15-20+% photo coverage tank

Simulating reactor IBDs in tank (seeing IBDs)

Need to understand backgrounds (this is still being updated and BUTTON running will help)

From current simulation work confident a 1kT tank will be able to detector reactor neutrinos



Expansion of Boulby gives us a unique opportunity to for growth

KamLAND 17" and 20" PMTs have been offered to the project


Physics goals:

Reactor neutrino studies


Supernova neutrinos

Diffuse Supernove neutrinos

Full at scale deployment of WbLS



# Thank you for listening




# Backup



# (Anti)Neutrino Detection

- Gadolinium doped fill media provides a much higher neutron capture cross section which allows better inverse beta decay detection. ( $\sim 163,000 \times$ ) – The second largest neutron capture cross section in nature.
- Inverse beta decay in some detector medium
- Neutron detection
- Can be fairly inexpensive for the volume
- $\bar{\nu}_e + p \rightarrow e^+ + n$



# Water Based Liquid Scintillator (WbLS)

## Cherenkov

- Directional information
  - Low attenuation – larger volumes possible
  - Particle ID at higher energies
- 
- Cherenkov threshold limits physics visible
  - Low light yield




Image adapted from: UC Davis Neutrino Group – Water based liquid scintillator

## WbLS

- Directional information
  - Lower attenuation than LS allowing larger volumes
  - Higher light yield than water
- 
- Unproven at scale -> BUTTON
  - Specific separation and cleansing system required
  - Waste Management

## Scintillation

- High light yield
  - No Cherenkov threshold
  - Good energy and position resolution
- 
- High attenuation limiting volume
  - Higher cost
  - Little to no directionality
  - More costly waste management

# BUTTON Calibration


## Requirements:

- Need to deploy radioactive sources anywhere in the BUTTON tank safely, cleanly, and do so with very constrained headroom limitations in the Boulby Underground Lab main hall.


## Solution:

- Sources deployed from a removable cassette inside a permanently mounted sealed box.
- 5 deployment ports available at top of tank.


## Untagged AmBe and 2.6 MeV $^{208}\text{Tl}$



## tagged AmBe



## Detector top calibration design and Prototype testing



## Prototyping and initial steps




- Prototype deployment cassette - testing now AmBe source to UK April 2025
- Untagged gamma and neutron source containers, deployment April/May 2025.

## Once cassette prototyping completed


- Adjust designs if needed, build finalized designs and test and deploy at BUTTON (May/June)
- Tagged AmBe deployment device to UK mid 2025.

# BUTTON Diagnostics and Software

## Diagnostics: fluid attenuation/scattering



## Simulation and Software







- RAT-PAC2 simulation package
- Implementation of BUTTON PMT encapsulation features, and consult on use of new RATPAC2 features
- EOS/BUTTON commonalities will ensure compatibility, leverage co-developed software


# Magnetic field compensation

## COMSOL simulation


- PMT response is dependent upon external magnetic fields.
- The background magnetic field was measured in the experimental area.
- Simulations of magnetic coils to compensate for these background fields have been undertaken.
- A complete compensation system has been proposed which increases PMT relative output by up to 20% (0.35 Gauss to < 0.1 Gauss).





# Non-reflective liner




Simply zip tied to the inside of the PSUP frames, with radial liners overlapped



8 x "radial liners"




8 x  
"top/bottom  
liners"




## Liners cut from polythene


- Specific material soak tested in concentrated Gd solution
- Soaked in America in WbLS
- UV-Vis tested the "contaminated" water samples
- UV transmission tested
- Several companies test cut samples

# Internal manifolds








plumbing	Tees	90 degree	Union	Other
Lower outer manifold	3	6	4	3m pipe
Upper outer manifold	3	6	4	
Upper inner manifold	3	9	4	
Plumbing across lab	1	10	10	<ul style="list-style-type: none"> <li>Flex hose</li> <li>Hose barbed fitting</li> <li>10m PVDF pipe</li> </ul>
<b>Total</b>	<b>10</b>	<b>35</b>	<b>25</b>	<b>13m</b>
				Unions into 3/4" bsp SS316



Internal plumbing final plan



L1 = L2 for symmetric flow

# Inner plumbing - irrigation

